parakeet communities

INTERNAL CONFIDENTIAL DOCUMENT

Quickbase + FastField Build Specification

Home Ordering, Delivery & Set — Workflow #001

Parakeet Communities · Internal · Confidential

VERSION	DATE	STATUS
1.2	August 2026	Active

> ***v1.2 Changes:*** *Adds Section 3A — Cascading Dropdown Architecture (system-wide standard for Community → Lot → Asset filtering across all QB and FastField forms). Adds Lot Status automation rules (LS-1 through LS-6). Adds Open Items O11–O12. All v1.1 content preserved.*

Table of Contents

1. Overview 2
2. Roles Reference 3
3. Quickbase Data Model 3
3.1 Table Architecture 3
3.2 Home Orders (Master) 4
3.3 Lots 6
3.4 Workflow Tasks 7
3.5 Delivery Records 7
3.6 Construction Inspection Records 8
3.7 Ops Readiness Records 9
3.8 Listing Records 10
3A. Cascading Dropdown Architecture 10
4. Quickbase Forms & Views 13
5. Quickbase Automations 14
6. FastField Forms 16
6.1 Form 1: Home Delivery Confirmation 16
6.2 Form 2: Construction Inspection (89 Items) 16
6.3 Form 3: Ops & Sales Readiness (71 Items) 19
6.4 Form 4: Listing Form 22
7. QB ↔ FastField Integration 22
8. Workflow Gate Rules
9. Build Sequence
10. Open Items & Decisions Needed

SECTION 01

Overview

Purpose

This document defines the complete Quickbase and FastField build for the Home Ordering, Delivery & Set workflow. It is the **single source of truth** for the configuration. Use it to build, QA, and train staff on the system.

Version 1.2 incorporates the actual 89-item Construction Installation Checklist and 71-item Ops & Sales Readiness Checklist submitted by the field teams, expands the workflow to 12 stages, and establishes the system-wide Cascading Dropdown Architecture (Section 3A) as the standard for all Community → Lot → Asset selections across every Quickbase and FastField form.

Scope

Covers all 12 stages from **Infill Need Identified** through **Listed — Complete**. Rent Manager (RM) remains the system of record for asset records and financial data — this build *complements* RM, it does not replace it.

BOUNDARY	DETAIL
In scope	All 12 workflow stages; QB tables, forms, automations, gates; FastField forms; FF ↔ QB integration
Out of scope	Rent Manager asset record creation; marketing execution after listing; other workflows (Rehab, Resident Mgmt)

Systems Involved

SYSTEM	ROLE IN THIS WORKFLOW
Quickbase	Workflow engine, status tracking, task assignment, internal notifications, gate enforcement
FastField	Field-capture forms — delivery confirmation, construction inspection, ops readiness, listing

Microsoft 365 / Teams	Notification delivery for automation-triggered alerts
Claude (via Ops Coordinator)	Invoice extraction (Melanie uses Claude to extract invoice data for QB entry)

Version History

VERSION	DATE	CHANGES
1.0	Aug 2026	Initial build specification — 11 stages, 6 QB tables, 3 FastField forms, 11 automations, 8 gate rules
1.1	Aug 2026	Actual 89-item Construction and 71-item Ops checklists incorporated; workflow expanded to 12 stages; 7 QB tables, 4 FastField forms, 14 automations, 9 gate rules; all MRB references removed
1.2	Aug 2026	Section 3A added — Cascading Dropdown Architecture (system-wide standard); Lot Status automation rules LS-1 through LS-6 added; Open Items O11–O12 added

SECTION 02 Roles Reference

ROLE	ABBREVIATION	NAME / PERSON	QB ACCESS LEVEL
Director of Sales & Marketing	Sales	Process Owner	Full Edit
Asset Management / RM Admin	Asset Mgmt	Justin	Full Edit
Operations Coordinator	Ops Coord	Melanie	Edit (assigned tasks)
Facility Manager	Facility Mgr	—	Edit (assigned tasks)
Operations	Ops	—	Edit (assigned tasks)
Director of Construction	Construction	John Clark	Full Edit
Community Manager / Sales Rep	Comm Mgr	—	Edit (assigned tasks)
Accounting	Accounting	—	Edit (assigned tasks)
System Administration	Sys Admin	—	Admin

SECTION 03 Quickbase Data Model

3.1 Table Architecture

The Quickbase build uses a relational, multi-table model. Each table has a specific job. They are linked so that one home order record drives all downstream tasks and child form records. The spine of the entire workflow is the Home Orders table — one record = one home.

#	TABLE NAME	PURPOSE
1	Home Orders	Master record for each home — one record per home; spine of the entire workflow
2	Lots	Reference table for all lots across all communities; drives cascading dropdown filters
3	Workflow Tasks	Child records tracking every assigned task per home order; auto-generated by automations at each stage
4	Delivery Records	FastField delivery form data, linked to Home Order; triggered by Form 1 submission
5	Construction Inspection Records	FastField Construction checklist data, linked to Home Order; technical sign-off by Director of Construction
6	Ops Readiness Records	FastField Ops & Sales readiness checklist data; show-readiness confirmation after Construction sign-off
7	Listing Records	FastField listing form data, linked to Home Order; triggers Listed — Complete stage

3.2 Table: Home Orders (Master)

The spine of the entire workflow. Every other table links back to it. One record = one home. Controls the 12-stage Workflow Stage field that governs all automation triggers and gate rules.

Identity & Property

FIELD NAME	FIELD TYPE	OPTIONS / NOTES	REQUIRED	WHO ENTERS
Record ID#	Auto-number	System generated	*Auto*	System
Home Order #	Formula-Text	`HO-YYYY-###`	*Auto*	System
Community / Property	Relationship → Communities	Selected first — drives Lot filter (see Section 3A)	Yes	Sales
Lot Number	Relationship → Lots	Filtered: only lots in selected Community where Lot Status = Available	Yes	Sales
Infill Reason	Multiple Choice	Occupied Lot Turnover / Vacant Lot / Demo Lot	Yes	Asset Mgmt
Date Created	Date	Auto-set on record creation	*Auto*	System
Created By	User	Auto-set	*Auto*	System

Manufacturer & Home Details

FIELD NAME	FIELD TYPE	OPTIONS / NOTES	REQUIRED	WHO ENTERS
Manufacturer	Multiple Choice	Cavco / Clayton / Skyline / Champion / Other (see O5)	Yes	Sales
Floor Plan Name	Text		Yes	Sales
Model	Text		No	Sales
Production Line	Text		Yes	Sales
Home Type	Multiple Choice	Single Wide / Double Wide / Triple Wide	Yes	Asset Mgmt
Setup Type	Multiple Choice	Piers / Runners / Full Slab / Stem Wall	No	Construction
Dimensions	Text	e.g. 16x76	No	Asset Mgmt
Square Footage	Numeric		No	Asset Mgmt
Bedrooms	Numeric		No	Asset Mgmt
Bathrooms	Numeric - Decimal		No	Asset Mgmt
Serial Number	Text	⚠ Required before advancing to Delivery Scheduled (Gate G5)	No initially	Asset Mgmt

Dates & Timeline

FIELD NAME	FIELD TYPE	NOTES	REQUIRED	WHO ENTERS
Order Date	Date		Yes	Sales
Online Date	Date	When home enters production	No	Sales
Offline Date	Date	When home leaves production	No	Sales

Estimated Delivery Date	Date	Triggers A4 notification when changed	No	Construction
Actual Delivery Date	Date		No	Construction / Ops
Set Date	Date		No	Construction
Construction Inspection Date	Date	Auto-set when Construction Inspection Record created	No	System / Construction
Ops Readiness Date	Date	Auto-set when Ops Readiness Record created	No	System / Facility Mgr
Listing Date	Date	Auto-set at listing	*Auto*	System

Financial

FIELD NAME	FIELD TYPE	NOTES	REQUIRED	WHO ENTERS
Purchase Price	Currency	Format: $1,234.56	Yes	Accounting
Purchase Date	Date	Format: mm/dd/yy	Yes	Accounting
Floorplan Line	Text		No	Accounting
Loan Number	Text		No	Accounting
Loan Amount	Currency		No	Accounting
Lender	Text		No	Accounting
Insurance Carrier	Text		No	Accounting
Insurance Policy #	Text		No	Accounting

Status & Stage

FIELD NAME	FIELD TYPE	OPTIONS / NOTES	REQUIRED	WHO ENTERS
Workflow Stage	Multiple Choice	12-stage list below — controlled by automations & gates	Yes	System / Sales
Status	Multiple Choice	Active / On Hold / Cancelled	Yes	Sales
Storage Required?	Checkbox	Triggers Automation A5 when checked	No	Construction
Storage Location	Multiple Choice	On Lot / Manufacturer / Community / Other	*Conditional*	Construction
Storage Start Date	Date	Set when storage begins	*Conditional*	Construction
Lot Fit Issue?	Checkbox	Flag if delivered home does not fit lot — triggers hard stop A9	No	Construction

Rent Manager Cross-Reference

FIELD NAME	FIELD TYPE	NOTES	REQUIRED	WHO ENTERS
RM Asset Record #	Text	Manual cross-reference to Rent Manager asset	No	Asset Mgmt
RM Unit #	Text	Manual cross-reference	No	Asset Mgmt
Internal Notes	Text Multi-line		No	Any
Last Updated	Date/Time	Auto	*Auto*	System
Last Updated By	User	Auto	*Auto*	System

Workflow Stage Values (12 stages)

#	STAGE NAME	#	STAGE NAME
1	Infill Need Identified	7	In Storage ★
2	Lot Due Diligence	8	Delivery Scheduled
3	Home Selected	9	Delivered
4	Order Placed	10	Home Set & Construction Inspection
5	File & Asset Setup	11	Ops & Sales Readiness
6	In Production	12	Listed — Complete

★ Stage 7 (In Storage) is conditional — activated only when Storage Required = Yes. Skip directly from Stage 6 → 8 for homes going straight to delivery without storage.

3.3 Table: Lots

Reference table. Populated once, maintained as lots change. **Lot Status is critical** — it drives cascading filters across all forms system-wide (see Section 3A).

FIELD NAME	FIELD TYPE	NOTES	REQUIRED	WHO ENTERS
Lot ID	Auto-number	System generated	*Auto*	System
Community	Relationship → Communities		Yes	Sys Admin
Lot Number	Text	Must be unique within community	Yes	Sys Admin
Lot Status	Multiple Choice	**Available / Occupied / Reserved / Demo** — must be kept current at all times; drives all cascade filters	Yes	System (auto) / Sys Admin
Has Active Asset	Formula-Checkbox	True if count of linked assets > 0 and Status ≠ Archived	*Auto*	System
Active Asset Status	Lookup	Pulls status field from the active linked asset record	*Auto*	System
Current Resident Name	Text	Updated at move-in / move-out	No	Asset Mgmt
Buildable Envelope	Text		No	Construction
Door Swing	Text		No	Construction
Electrical Details	Text		No	Construction
Water / Sewer Available	Checkbox		No	Construction
Site Survey Completed	Checkbox	Required for Gate G2	No	Construction
Site Survey Upload	File Attachment		No	Construction
Notes	Text Multi-line		No	Any

Lot Status Definitions

STATUS	DEFINITION & VISIBILITY RULES
AVAILABLE	Vacant lot, no active resident. *Appears in:* Move In lot filter, Vacant Lot selections, new Home Order form
OCCUPIED	Has active resident. *Appears in:* Move Out lot filter, inspections, incident reports

RESERVED	Committed but not yet moved in (e.g., home ordered, sale pending). *Excluded from* both Move In and Move Out filters
DEMO	Clearance / demolition lot. *Excluded from all* resident-facing forms

3.4 Table: Workflow Tasks

One record per task per home order. Each stage transition auto-generates its standard task set via automations A1–A7.

FIELD NAME	FIELD TYPE	NOTES	REQUIRED	WHO ENTERS
Task ID	Auto-number	System generated	*Auto*	System
Home Order	Relationship → Home Orders	Parent record	Yes	System
Task Name	Text	Auto-populated by automation templates	Yes	System
Task Category	Multiple Choice	Due Diligence / Order / Setup / Delivery / Inspection / Readiness / Listing	Yes	System
Assigned To	User	QB user account; auto-set by automation	No	System / Manager
Assigned Role	Multiple Choice	Role from Roles Reference (Section 2)	No	System
Due Date	Date	Auto-populated from Order Date offset by automation rule	No	System
Status	Multiple Choice	Not Started / In Progress / Complete / Blocked	Yes	Assigned user
Completed Date	Date		No	Assigned user
Completion Notes	Text Multi-line		No	Assigned user
Required Before Next Stage	Checkbox	Gate enforcement flag — checked tasks must be Complete before stage advances	No	System

3.5 Table: Delivery Records

Populated by FastField Form 1 (Home Delivery Confirmation). Submission of this record triggers Automation A7 which advances the stage to Delivered.

FIELD NAME	FIELD TYPE	NOTES	REQUIRED	WHO ENTERS
Delivery Record ID	Auto-number		*Auto*	System
Home Order	Relationship → Home Orders	Matched via Home Order # from FastField	Yes	System
Delivery Date	Date	Format: mm/dd/yy	Yes	FastField
Received By	User		Yes	FastField
Home Visually Confirmed	Checkbox		Yes	FastField
Serial Number Photo	File Attachment		Yes	FastField
Serial Number Confirmed	Text	Matches serial number in Home Orders record	Yes	FastField

Video Uploaded	Checkbox		Yes	FastField
Photos Uploaded	File Attachment	Minimum 5 photos required	Yes	FastField
Photo Count	Numeric	Minimum 5	Yes	FastField
Exterior Checklist Completed	Checkbox		Yes	FastField
Lot Fit Confirmed	Checkbox	If No → triggers Lot Fit Issue flag on Home Order	Yes	FastField
Delivery Notes	Text Multi-line		No	FastField
Submitted Via	Text	Always: FastField	Auto	System
Submission Timestamp	Date/Time	Auto-set on submission	Auto	System

3.6 Table: Construction Inspection Records

Populated by FastField Form 2 (Construction Inspection Checklist). Represents the technical sign-off by the Director of Construction. Must be approved before Form 3 can be started.

FIELD NAME	FIELD TYPE	NOTES	REQUIRED	BY
Inspection Record ID	Auto-number		Auto	System
Home Order	Relationship → Home Orders	Matched via Home Order #	Yes	System
Inspection Date	Date	Format: mm/dd/yy	Yes	FF
Inspected By	User	Director of Construction or designee	Yes	FF
Setup Type	Multiple Choice	Piers / Runners / Full Slab / Stem Wall	Yes	FF
City / State	Text		Yes	FF
Roof — Pass Count	Numeric	10-item section; auto-summed from FastField	Auto	FF
Roof — Fail Count	Numeric		Auto	FF
Underneath — Pass / Fail	Numeric	12-item section	Auto	FF
Exterior — Pass / Fail	Numeric	5-item section	Auto	FF
Interior — Pass / Fail	Numeric	27-item section	Auto	FF
Windows & Doors — Pass / Fail	Numeric	6-item section	Auto	FF
Electrical — Pass / Fail	Numeric	13-item section	Auto	FF
Plumbing — Pass / Fail	Numeric	16-item section	Auto	FF
Total Items Inspected	Numeric	89 total	Auto	System
Total Pass	Numeric		Auto	System
Total Fail	Numeric	If > 0 → triggers A11 (remediation task)	Auto	System
Total N/A	Numeric		Auto	System
All Items Pass or N/A	Formula-Checkbox	True when Total Fail = 0 → triggers A10 (advance stage)	Auto	System
Items Requiring Attention	Text Multi-line	Description of any failed items	No	FF
Construction Sign-Off	Checkbox	Final sign-off by Director of Construction	Yes	Construction

Sign-Off Date	Date		Yes	Construction
Full Inspection PDF	File Attachment	FastField generates and attaches automatically	Auto	FastField
Submitted Via	Text	Always: FastField	Auto	System

3.7 Table: Ops Readiness Records

Populated by FastField Form 3 (Ops & Sales Readiness Checklist). Completed after Construction sign-off is on file. Two signatures required: Facility Manager AND Community Manager / Sales Rep.

FIELD NAME	FIELD TYPE	NOTES	REQUIRED	BY
Readiness Record ID	Auto-number		Auto	System
Home Order	Relationship → Home Orders	Matched via Home Order #	Yes	System
Inspection Date	Date	Format: mm/dd/yy	Yes	FF
Home Type	Multiple Choice	New Delivery / Rehab / Turnover	Yes	FF
Inspection Type	Multiple Choice	Weekly / Pre-Listing / Pre-Move-In	Yes	FF
Construction Sign-Off On File	Checkbox	Must be checked; prerequisite before form can be submitted	Yes	FF
Completed By — Facility Mgr	User		Yes	FF
Completed By — Comm Mgr / Sales Rep	User		Yes	FF
Utility — Fail Count	Numeric	10-item section	Auto	FF
Mechanical & Safety — Fail Count	Numeric	5-item section (excludes utility alert item per O9)	Auto	FF
Exterior — Fail Count	Numeric	8-item section	Auto	FF
Entry / Windows / Doors — Fail Count	Numeric	6-item section	Auto	FF
Kitchen — Fail Count	Numeric	9-item section	Auto	FF
Bathrooms — Fail Count	Numeric	7-item section	Auto	FF
Interior Presentation — Fail Count	Numeric	8-item section	Auto	FF
Cleanliness — Fail Count	Numeric	8-item section	Auto	FF
Total Fail Count	Numeric	If > 0 → triggers A13 (remediation task)	Auto	System
Home Ready for Listing	Checkbox	True when Total Fail = 0 → triggers A12 (advance to pre-listing)	Yes	FF
Issue Description / Escalation Notes	Text Multi-line	Required if any fails	No	FF
Regional Mgr Notified	Checkbox	Escalation tracking	No	FF
Vendor Notified	Checkbox	Escalation tracking	No	FF
Work Order Submitted	Checkbox	Escalation tracking	No	FF
Follow-Up Date	Date	Escalation tracking	No	FF
Facility Mgr Sign-Off	Checkbox		Yes	Facility Mgr
Comm Mgr / Sales Rep Sign-Off	Checkbox		Yes	Comm Mgr

Full Readiness PDF	File Attachment	FastField auto-generated	*Auto*	FastField
Submitted Via	Text	Always: FastField	*Auto*	System

3.8 Table: Listing Records

Populated by FastField Form 4 (Listing Form). Submission with all 7 pre-listing items confirmed triggers Automation A14 – stage advances to Listed – Complete and team notification is sent.

FIELD NAME	FIELD TYPE	NOTES	REQUIRED	BY
Listing Record ID	Auto-number		*Auto*	System
Home Order	Relationship → Home Orders	Matched via Home Order #	Yes	System
Listed By	User		Yes	Sales
Listing Date	Date	Format: mm/dd/yy	Yes	Sales
Construction Inspection Approved	Checkbox	Pre-listing verification item 1 of 7	Yes	Sales
Ops & Sales Readiness Approved	Checkbox	Pre-listing verification item 2 of 7	Yes	Sales
Insurance Active in RM	Checkbox	Pre-listing verification item 3 of 7	Yes	Accounting
Loan Documents Uploaded to RM	Checkbox	Pre-listing verification item 4 of 7	Yes	Accounting
Serial Number Confirmed in RM	Checkbox	Pre-listing verification item 5 of 7	Yes	Asset Mgmt
Asset Status Updated in RM	Checkbox	Pre-listing verification item 6 of 7	Yes	Asset Mgmt
Manufacturer Packet Confirmed	Checkbox	Pre-listing verification item 7 of 7	Yes	Sales
All Pre-Listing Items Complete	Formula-Checkbox	True when all 7 items above = Yes. Triggers A14.	*Auto*	System
Internal Notification Sent	Checkbox	Auto-set by Automation A14	*Auto*	System
Notes	Text Multi-line		No	Sales

SECTION 3A NEW IN V1.2 Cascading Dropdown Architecture

System-Wide Standard

SYSTEM-WIDE STANDARD – NO EXCEPTIONS. Every form in Quickbase and FastField that includes Community, Lot, or Asset selection MUST follow these rules. This applies to all 15+ forms system-wide, not just Workflow #001.

The Hierarchy

```
Community
    └── Lot              (filtered by Community)
            └── Asset    (filtered by Lot + Asset Status)
```

Each tier is a **relationship field** (never free-text). Selecting a value at one tier immediately narrows the options at the next tier. Community is always unfiltered. Lot is always filtered to the selected Community, then further filtered by Lot Status based on form context. Asset is always filtered to the selected Lot, then further filtered by Asset Status based on form context.

Context-Specific Filter Rules – All Forms

This table is the authoritative reference. When building any form, find the form in this table and apply the filter exactly as specified.

FORM / CONTEXT	COMMUNITY	LOT FILTER	ASSET FILTER	NOTES
Home Order (new)	All communities	Lots in Community where Lot Status = AVAILABLE	No asset — new home being ordered	Lot locked → Reserved on record creation (LS-1)
Home Listing Request	All communities	All lots in Community	All assets on Lot	Any lot can request a listing
Home Listing Confirmation	All communities	All lots in Community	Assets where Asset Status = Listed	Confirming an already-listed asset only
Offer to Purchase / Rent	All communities	Lots where active asset status = Listed	Listed assets on Lot	Only purchasable / rentable homes shown
Utility Request	All communities	All lots in Community	No asset selection needed	Utility is lot-level, not asset-level
Move In	All communities	Lots where Lot Status = AVAILABLE	If community-owned home sale → listed assets on Lot; else no asset field	See Move In / Move Out full cascade below
Move Out	All communities	Lots where Lot Status = OCCUPIED	Assets on selected Lot (the home being vacated)	See Move In / Move Out full cascade below
Move Out Inspection	All communities	Lots where Lot Status = OCCUPIED	Assets on Lot	Only occupied lots can have a move-out inspection
Resident Information Sheet	All communities	All lots in Community	No asset selection needed	Data entry form
Rehab Walkthrough	All communities	Lots where active asset status = In Rehab	Rehab assets on Lot	Only rehab-stage homes shown
Community Site Visit	Community only	N/A	N/A	Community-level form — no lot or asset selection
Weekly Maintenance	Community only	N/A	N/A	Community-level form
Incident Report	Community only	Optional — all lots	N/A	Location is free-text or optional lot selection
Month End Checklist	Community only	N/A	N/A	Community-level form
Monthly Equipment & Inventory	Community only	N/A	N/A	Community-level form
Construction Inspection (FastField)	All communities	Lots with Workflow Stage = Home Set & Construction Inspection	Asset linked to QB Home Order	Pre-populated from QB Home Order record via launch link — field staff do not select manually
Ops & Sales Readiness (FastField)	All communities	Lots with Workflow Stage = Ops & Sales Readiness	Asset linked to QB Home Order	Pre-populated from QB Home Order record via launch link

Move In / Move Out — Full Cascade Logic

> This is the most complex filter scenario. The Lot list re-filters dynamically based on the Move In vs. Move Out selection. Get this wrong and incorrect lots are presented to users.

Step 1: User selects Community → all lots in that Community load.

Step 2: User selects Move In *or* Move Out → Lot list immediately re-filters:

SELECTION	LOT FILTER APPLIED	ASSET FILTER
Move In	Lot Status = AVAILABLE (vacant lots only)	If "Community Owned Home Sale?" = YES → show listed assets on Lot. If NO → no asset field shown
Move Out	Lot Status = OCCUPIED (occupied lots only)	Assets on selected Lot (the home being vacated)

Why this matters: Without this filter, a Move In form could accidentally select an already-occupied lot. Without it on Move Out, it could target a vacant lot that has no one to move out. The filter eliminates those errors at the data entry point — not after the fact in a report.

QB Implementation Method

Relationships Required

#	RELATIONSHIP	NOTES
1	Communities → Lots (one-to-many)	1 Community has many Lots
2	Lots → Home Orders (one-to-many)	1 Lot has many Home Orders over time
3	Lots → Residents table (one-to-one active)	1 Lot has 1 active Resident (future table)
4	Lots → Assets table (one-to-many)	1 Lot has many Assets over time; 1 active at a time

QB Form Configuration — Step by Step

1. On every QB form, set the Lot field as a **relationship lookup field** (not free-text)
2. In the Lot field settings, enable **"Filter related records"** → filter where Community field on Lot record matches the Community field on the current form
3. For status-based filters: add a **second filter condition** — Lot Status = [target value from the reference table above]
4. For Asset field: same pattern — filter where Lot field matches, plus Asset Status = [target value]
5. Test every form: select a Community, verify only correct Lots appear; select a Lot, verify only correct Assets appear

Lot Status Must Be Current — QB Automations Maintain It

If Lot Status falls out of sync, filters break and incorrect lots appear in forms. These automations keep it accurate automatically.

RULE	TRIGGER	LOT STATUS CHANGE	NOTES
LS-1	New Home Order created for a lot	Available → RESERVED	Lot committed to this home order; removed from new order filter
LS-2	Home Order cancelled	Reserved → AVAILABLE	Lot freed; re-appears in new order and Move In filters
LS-3	Move In request processed	Reserved → OCCUPIED	Resident has moved in; now appears in Move Out filter
LS-4	Move Out request processed	Occupied → AVAILABLE	Lot is vacant again; re-appears in Move In and new order filters
LS-5	Stage → Listed — Complete	No change (stays Reserved)	Lot remains Reserved until Move In is processed
LS-6	Home delisted with no active resident	Reserved → AVAILABLE	Lot freed if listing is cancelled before move-in

FastField Implementation Method

OPTION	METHOD	HOW IT WORKS	RECOMMENDED FOR

Option A	QB API Sync (preferred)	FastField pulls live data from QB via API on form open. Community selection triggers a filtered call to QB Lots table. Requires FastField Enterprise or API integration setup.	Office forms: Listing, Utility Request
Option B	Pre-populated Launch Link (recommended for field forms)	QB generates a unique FastField form launch URL that pre-populates Community, Lot, and Home Order # from the QB record. Field staff don't select – values are pre-filled. Eliminates the filtering problem entirely for field forms.	Field forms: Delivery Confirmation, Construction Inspection, Ops Readiness – launched from the specific QB Home Order record
Option C	CSV Sync (fallback / initial launch)	QB exports a filtered Lots CSV daily. FastField imports it as a data source. Community → Lot cascade works; status-based filtering is limited to the last export cycle.	Initial launch fallback for all forms; upgrade to Option A over time

Note on Option B: Requires QB Pipelines or API to generate the FastField launch URL from a QB record. See Open Item O11 for setup requirements.

Asset Status Values – Filter Visibility Reference

ASSET STATUS	VISIBLE IN
Ordered	Home Order forms only
In Production	Home Order forms only
Delivered	Construction Inspection forms
In Storage	Home Order forms / Storage tracking views
Home Set	Construction Inspection forms, Ops & Sales Readiness forms
Listed	Offer to Purchase / Rent form, Listing Confirmation form
Active / Occupied	Move Out Inspection, Inspections, Rehab forms
In Rehab	Rehab Walkthrough form only
Archived	Hidden from ALL forms – never shown in dropdowns

SECTION 04 Quickbase Forms & Views

4.1 Forms

#	FORM NAME	USED BY	KEY FIELDS / NOTES
Form 1	New Home Order	Sales	Community, Lot Number (filtered: Available lots only per Section 3A), Infill Reason, Manufacturer, Floor Plan Name, Production Line, Order Date. Triggers LS-1 on save.
Form 2	Lot Due Diligence Entry	Operations / Construction	All Lot table fields, pre-linked to the lot on the Home Order. Gate G2 requires this to be marked complete before stage advances to Home Selected.
Form 3	Home Details & Asset Setup	Asset Mgmt / Sales	Model, Setup Type, Dimensions, Square Footage, Bedrooms, Bathrooms, Home Type, RM Asset Record #, Purchase Price, Purchase Date. First time RM cross-reference fields are populated.

Form 4	Date Management	Sales (updated repeatedly)	Online Date, Offline Date, Estimated Delivery Date. Triggers Automation A4 (department-wide date change notification email) on every save where any date field changes.
Form 5	Storage Entry	Construction	Storage Required (checkbox), Storage Location, Storage Start Date. Conditional — only accessible when Storage Required = checked. Triggers A5.
Form 6	Delivery Coordination	Construction	Estimated Delivery Date update, delivery vendor notes, assigned receiver. Advances stage to Delivery Scheduled.
Form 7	Post-Delivery Asset Update	Asset Mgmt	Actual Delivery Date, documentation status checklist, RM confirmation fields, Lot Fit Issue flag. Completed after FastField Form 1 is submitted.
Form 8	Insurance & Loan Entry	Accounting	Floorplan Line, Loan Number, Loan Amount, Lender, Insurance Carrier, Insurance Policy #. Required for Gate G4.
Form 9	Set & Utility Coordination	Construction	Set Date, utility accounts live confirmation. Completed after home is set on the lot.
Form 10	Pre-Listing Final Gate	Sales	All 7 pre-listing checklist items — hard validation: all must = Yes before form saves. Links to Listing Records table. Triggers A14.

4.2 Views / Dashboards

#	VIEW NAME	PRIMARY USER	DESCRIPTION
View 1	Pipeline Board	All roles	Kanban by Workflow Stage — color-coded: GREEN on track, YELLOW approaching deadline, RED overdue or blocked
View 2	My Tasks	All assigned users	Per-user filtered task list, sorted by due date ascending. Only shows tasks assigned to the logged-in user.
View 3	Sales Master Tracker	Sales	All active Home Orders with key dates inline-editable. Sortable by stage, community, manufacturer, or date.
View 4	Overdue / Blocked Alert	Management	Filtered: all tasks where Status = Blocked OR Due Date < today AND Status ≠ Complete. Management escalation view.
View 5	Storage Aging Report	Construction / Sales	Days in storage calculated (today − Storage Start Date). Homes > 30 days flagged RED. Sorted by days descending.
View 6	Accounting Tracker	Accounting	Financial fields view — Purchase Price, Loan Amount, Insurance, filterable by "action needed" flag. Inline editable for Accounting fields only.

SECTION 05 Quickbase Automations

14 workflow automations (A1–A14) plus 6 Lot Status automations (LS-1 through LS-6). All automations are QB-native unless noted.

A1–A14: Workflow Automations

#	TRIGGER	ACTION	RECIPIENT	NOTES
A1	New Home Order record created	Create Stage 1–2 task set (lot due diligence tasks); set Lot Status → Reserved (LS-1)	Assigned roles	Lot locked out of other new orders immediately
A2	Stage → Home Selected	Create Stage 3–4 task set (order confirmation, asset setup tasks)	Sales, Accounting	
A3	Stage → Order Placed	Create Stage 5 task set (file & asset setup tasks)	Sales, Asset Mgmt, Ops Coord	

A4	Online Date, Offline Date, or Estimated Delivery Date changed	Send date change notification email to all departments	Regional, Ops, Accounting, Asset Mgmt, Construction	Standard template email — see Open Item O8 for draft
A5	Storage Required = checked	Create storage task; flag record for Storage Aging view	Construction, Asset Mgmt	Activates Stage 7 (In Storage) path
A6	Storage days > 30 (daily check)	Send storage aging alert	Construction, Sales, Ops	Calculated: today − Storage Start Date > 30
A7	Delivery Records child record created (FastField Form 1 submitted)	Stage → Delivered; create post-delivery task set	Asset Mgmt, Accounting, Sales	Triggered by FastField webhook or CSV import
A8	Serial Number blank when Stage = Delivery Scheduled	Warning notification: serial number missing before delivery	Sales, Asset Mgmt	Non-blocking warning — not a hard stop
A9	Lot Fit Issue = checked	Immediate alert; block stage advancement; create escalation task	Sales, Asset Mgmt, Accounting	**Hard stop** — stage cannot advance until resolved
A10	Construction Inspection record created AND All Items Pass = true	Stage → Ops & Sales Readiness; notify inspection team	Facility Mgr, Comm Mgr, Sales	Green path — all 89 items pass or N/A
A11	Construction Inspection record created AND Total Fail > 0	Create remediation task assigned to Construction; block stage	Construction	Red path — at least one item failed
A12	Ops Readiness record created AND Home Ready = true	Stage → pre-listing; create listing task	Sales, Asset Mgmt	Green path — all 71 items pass
A13	Ops Readiness record created AND Total Fail > 0	Create remediation task; block stage	Ops, Construction, Sales	Red path — at least one item failed
A14	Listing Records created AND All Pre-Listing Items Complete = true	Stage → Listed — Complete; send team notification; Lot Status → Reserved (stay, per LS-5)	All roles	Final stage trigger. All 7 pre-listing gates must be Yes.

LS-1 through LS-6: Lot Status Automations NEW IN V1.2

These automations maintain Lot Status accuracy in real time. Without them, cascading dropdown filters (Section 3A) will show incorrect lots to users. These are not optional.

RULE	TRIGGER	LOT STATUS CHANGE	NOTES
LS-1	New Home Order record created (linked to a Lot)	Available → RESERVED	Lot committed to this home order; removed from new order and Move In filters
LS-2	Home Order Status changed to Cancelled	Reserved → AVAILABLE	Lot freed; re-appears in applicable filters immediately
LS-3	Move In request processed / approved in QB	Reserved → OCCUPIED	Resident has moved in; lot now appears in Move Out filter only
LS-4	Move Out request processed / approved in QB	Occupied → AVAILABLE	Lot is vacant; re-appears in Move In and new Home Order filters
LS-5	Stage → Listed — Complete	No change — stays RESERVED	Lot stays Reserved until Move In is processed (LS-3). This is correct — do not change to Available.

LS-6	Home delisted with no active resident on lot	Reserved → AVAILABLE	Listing cancelled before move-in; lot freed back to available pool

SECTION 06 FastField Forms

4 Forms — Workflow #001

Community / Lot / Home pre-populated via QB launch link — field staff do not manually select these on any field-capture form. QB generates a pre-populated FastField URL from the Home Order record. See Section 3A (Option B) and Open Item O11.

6.1 Form 1: Home Delivery Confirmation

Completed by: Construction or Operations on-site at delivery. **QB target table:** Delivery Records. **Matching key:** Home Order #. Submission triggers Automation A7 (stage → Delivered).

SECTION	FIELDS	REQUIRED
A — Home ID	Home Order # (pre-populated), Community (pre-populated), Lot # (pre-populated), Delivery Date	Yes — all
B — Serial Number	Serial Number (as shown on VIN plate), Serial Number Photo (attachment)	Yes — both
C — Photo & Video	Walkaround Video uploaded (Yes/No), Exterior Photo Set (minimum 5 photos), Photo count verified	Yes — all
D — Exterior Condition	Exterior checklist — transportation damage check, siding, eaves, windows, roof visual, foundation area. Response: Pass / Fail / N/A + Notes field per item	Yes — all
E — Lot Fit	Home fits lot as ordered (Yes/No). If No: description of fit issue (text), Lot Fit Issue flag auto-set on QB Home Order record, Automation A9 triggered	Yes
F — Submission	Received By (name), Inspector signature, Submission timestamp (auto)	Yes

6.2 Form 2: Construction Inspection Checklist (89 Items)

Completed by: Director of Construction or designated inspector. **Prerequisite:** Home must be set before this form is started. **QB target table:** Construction Inspection Records. **Matching key:** Home Order #. Submission triggers A10 (all pass) or A11 (any fail).

INSTRUCTION: Construction sign-off must be on file before Ops & Sales Readiness form can be started. Physically verify every item — if it has not been checked, it is not confirmed. Response = Yes / No / N/A + Notes / Observations field per item.

Header Fields (pre-populated from QB Home Order):

Property / Community (pre-populated)	Lot # (pre-populated)
Home Model (pre-populated)	Serial Number (pre-populated)
City / State	Type of Setup: Piers / Runners / Full Slab / Stem Wall
Inspected By	Date (auto)

#	ASSESSMENT ITEM	YES	NO	N/A
SECTION A — ROOF: STRUCTURAL INTEGRITY & INSTALLATION (10 ITEMS)				
1	All shingles properly installed	☐	☐	☐
2	All debris removed from roof	☐	☐	☐
3	Ridge vent installed properly: peaked, nailed, and sealed	☐	☐	☐

4	Close-up felt not over tar tabs	☐	☐	☐
5	No exposed fasteners	☐	☐	☐
6	All shingles and vents are damage-free	☐	☐	☐
7	Eaves and fascia are straight	☐	☐	☐
8	Windbreaker holes are tarred	☐	☐	☐
9	Vents, boots, flues, and extensions are secured and sealed properly	☐	☐	☐
10	Shingle flashing properly installed	☐	☐	☐
SECTION B — UNDERNEATH HOME: STRUCTURE, BLOCKING & MECHANICAL RUNS (12 ITEMS)				
11	Main beam, centerline, and perimeter are properly blocked	☐	☐	☐
12	Marriage line seal properly secured	☐	☐	☐
13	Wedges are tight	☐	☐	☐
14	A/C ducts properly suspended, attached, and installed	☐	☐	☐
15	Sewer crossovers connected and leak-free	☐	☐	☐
16	Sewer drain pipes properly sloped and fully installed	☐	☐	☐
17	Water crossovers connected and leak-free	☐	☐	☐
18	Bottom board is damage-free; any repairs taped and stapled	☐	☐	☐
19	Windows / ext / doors properly blocked	☐	☐	☐
20	Electrical crossovers connected	☐	☐	☐
21	Dryer vent installed and vented to outside	☐	☐	☐
22	Access board reinstalled after inspection	☐	☐	☐
SECTION C — EXTERIOR: STRUCTURAL & TRANSPORTATION DAMAGE CHECK (5 ITEMS)				
23	Close-up boards properly fastened	☐	☐	☐
24	Lap siding properly installed and damage-free	☐	☐	☐
25	Close-up exterior siding properly installed	☐	☐	☐
26	Exterior transportation damage-free	☐	☐	☐
27	GFI covers and hose bibbs are damage-free	☐	☐	☐
SECTION D — HOME INTERIOR: INSTALLATION QUALITY (27 ITEMS)				
28	Mate line doors and baseboard installed	☐	☐	☐
29	Floors inspected for squeaks	☐	☐	☐
30	Loose trim secured	☐	☐	☐
31	Wall panels inspected for blemishes, cuts, and damage	☐	☐	☐
32	Ceilings inspected throughout home	☐	☐	☐
33	Countertops inspected for damage and caulking	☐	☐	☐
34	Self-edge inspected for damage and caulking	☐	☐	☐
35	Appliances unpacked, level, and inspected for damage	☐	☐	☐
36	Cabinet doors inspected and adjusted	☐	☐	☐
37	Cabinet doors touched up if needed (putty, stain)	☐	☐	☐
38	Cabinet drawers inspected and adjusted	☐	☐	☐

39	Cabinet drawers touched up if needed (putty, stain)	☐	☐	☐
40	Face frames inspected for damage	☐	☐	☐
41	Face frames touched up if needed (putty, stain)	☐	☐	☐
42	Cabinet tops inspected for protruding nails, screws, cleanliness	☐	☐	☐
43	Shelves correct size and mounted properly to wall	☐	☐	☐
44	Fiberglass tub and showers inspected for chips or damage	☐	☐	☐
45	Caulk shower and tubs as needed	☐	☐	☐
46	Toilets and seats not cracked or scratched	☐	☐	☐
47	Toilet properly bolted to the floor	☐	☐	☐
48	Faucet fixtures and sinks are damage-free	☐	☐	☐
49	Faucet fixtures and sinks are properly installed	☐	☐	☐
50	Lavatory, shower, and hose bibb faucets function correctly	☐	☐	☐
51	Can lights inspected for securement	☐	☐	☐
52	Overhead ducts operating properly	☐	☐	☐
53	Ship-loose vinyl flooring installed across mate line	☐	☐	☐
54	Riser cavity properly connected and sealed	☐	☐	☐
SECTION E — WINDOWS & DOORS: OPERATION & SECURITY (6 ITEMS)				
55	Interior doors operational, hardware properly installed	☐	☐	☐
56	Exterior doors operational, screens and storm door installed	☐	☐	☐
57	Locks and keys operational	☐	☐	☐
58	Windows operational, screens installed, blinds functional	☐	☐	☐
59	Interior doors squared with casing aligned	☐	☐	☐
60	Interior doors caulked and painted if needed	☐	☐	☐
SECTION F — ELECTRICAL CHECK (13 ITEMS)				
61	Switch plates and receptacles straight	☐	☐	☐
62	Panel box and breakers inspected	☐	☐	☐
63	GFI breakers operate properly	☐	☐	☐
64	All receptacles operate properly	☐	☐	☐
65	All light switches operate properly	☐	☐	☐
66	All can lights operate properly	☐	☐	☐
67	Refrigerator operating properly	☐	☐	☐
68	Range operating properly	☐	☐	☐
69	Dishwasher operating properly	☐	☐	☐
70	Water heater operating properly	☐	☐	☐
71	Smoke detectors tested and function properly — spacer removed	☐	☐	☐
72	All bath fans functional	☐	☐	☐
73	Whole-house vent fan functional	☐	☐	☐
SECTION G — PLUMBING CHECK (16 ITEMS)				

74	Pressure test all water lines	☐	☐	☐
75	Adjust all commodes	☐	☐	☐
76	Clean out all faucet aerators	☐	☐	☐
77	Check all P-traps for leaks	☐	☐	☐
78	Check all fresh water lines for leaks	☐	☐	☐
79	Check under all sinks and tub / showers with accesses for leaks	☐	☐	☐
80	Check commodes for leaks – flush to test	☐	☐	☐
81	Check dishwasher for leaks	☐	☐	☐
82	Check icemaker line for leaks	☐	☐	☐
83	Check hose bibbs for leaks	☐	☐	☐
84	Check water heater for leaks	☐	☐	☐
85	Proper start of water heater per manufacturer's instructions	☐	☐	☐
86	Inspect water heater compartment for cleanliness	☐	☐	☐
87	Ensure all access doors work properly	☐	☐	☐
88	Access doors closed back up after inspection	☐	☐	☐
89	Sewer function test complete – home sinks brought to flood level	☐	☐	☐

☐ APPROVED – ALL ITEMS CONFIRMED	☐ ITEMS REQUIRING ATTENTION – SEE NOTES
All items Yes or N/A. No open items.	Escalate to responsible party before proceeding to Ops Readiness.

Sign-off: Director of Construction – Installation Sign-Off: _____ Date: _____

6.3 Form 3: Ops & Sales Readiness Checklist (71 Items)

Completed by: Facility Manager (Sections A–C and J) + Community Manager / Sales Rep (Sections D–I). **Prerequisite:** Construction sign-off must be on file. **QB target table:** Ops Readiness Records. Triggers A12 (all pass) or A13 (any fail).

> **INSTRUCTION:** Physically verify every item – if it has not been checked, it is not confirmed. Response = Yes / No / N/A + Notes / Observations field per item. **Note on item 14 (Rehab Utility):** Utility alert submitted immediately if any utility is off or missing – do not delay. Process for alert to be confirmed (see Open Item O9).

Header Fields (pre-populated from QB Home Order):

Property / Community (pre-populated)	Home / Unit # (pre-populated)
Home Type: New Delivery / Rehab / Turnover	Inspection Type: Weekly / Pre-Listing / Pre-Move-In
Completed By (pre-populated)	Date (auto)
Construction Sign-Off on File? Yes / No (must be Yes to submit)	

#	ASSESSMENT ITEM	YES	NO	N/A
SECTION A – UTILITY VERIFICATION: PHYSICALLY CONFIRMED; NO ASSUMPTIONS (10 ITEMS)				
1	Water service is active	☐	☐	☐
2	All faucets tested and flowing properly	☐	☐	☐
3	Toilets flushed and functioning	☐	☐	☐
4	No visible plumbing leaks anywhere in home	☐	☐	☐

5	No standing water present inside or outside	☐	☐	☐
6	Power service is active	☐	☐	☐
7	Interior lights tested and functioning throughout	☐	☐	☐
8	Outlets functioning — spot check completed	☐	☐	☐
9	Main breaker inspected and switched ON	☐	☐	☐
10	Meter physically verified	☐	☐	☐
SECTION B — REHAB-SPECIFIC UTILITY VERIFICATION (MARK N/A IF NEW DELIVERY) (4 ITEMS)				
11	Water physically verified ON at meter	☐	☐	☐
12	Power physically verified ON at meter	☐	☐	☐
13	Main breaker checked and confirmed ON	☐	☐	☐
14	Utility alert submitted immediately if any utility is off or missing — do not delay; submit at time of discovery (see Open Item O9)	☐	☐	☐
SECTION C — MECHANICAL & SAFETY (5 ITEMS)				
15	A/C operating properly — adequate cooling / heating observed; home at comfortable temperature	☐	☐	☐
16	No unusual HVAC noises or issues identified	☐	☐	☐
17	No roof leaks or water stains visible	☐	☐	☐
18	No evidence of insects, rodents, or active pest concerns	☐	☐	☐
19	Smoke detectors present and functional	☐	☐	☐
SECTION D — EXTERIOR & CURB APPEAL (8 ITEMS)				
20	Home appears level and properly set — visible from road	☐	☐	☐
21	Exterior siding clean, undamaged, and consistent in appearance	☐	☐	☐
22	Exterior doors clean, set / sealed, damage-free — hardware presentable	☐	☐	☐
23	GFI covers and hose bibbs in place and undamaged	☐	☐	☐
24	No exterior trash or debris — inside or outside lot	☐	☐	☐
25	Steps, porches, and skirting are safe, secure, and presentable	☐	☐	☐
26	Windows secure, intact, and clean — treatments aligned	☐	☐	☐
27	No off-putting odors upon arrival at entry	☐	☐	☐
SECTION E — ENTRY, WINDOWS & DOORS (6 ITEMS)				
28	All exterior doors open, close, and lock smoothly	☐	☐	☐
29	Screens and storm door installed and in good condition	☐	☐	☐
30	Keys organized and available for showing	☐	☐	☐
31	All interior doors open and close properly — hardware installed and presentable	☐	☐	☐
32	All windows operate properly — screens installed	☐	☐	☐
33	Blinds and window treatments functional and consistent throughout	☐	☐	☐
SECTION F — KITCHEN (9 ITEMS)				
34	Countertops clean, damage-free, and properly caulked	☐	☐	☐
35	Cabinets clean inside and out — no odors, stains, or damage	☐	☐	☐
36	Cabinet doors and drawers open and close properly	☐	☐	☐

37	Sink clean, functional, and properly sealed	☐	☐	☐
38	Faucets operate properly with good water pressure	☐	☐	☐
39	Refrigerator clean, level, and operating — verify ice maker line connected if applicable	☐	☐	☐
40	Range / oven clean — all burners and elements working	☐	☐	☐
41	Dishwasher clean — cycle runs and completes	☐	☐	☐
42	No odors from any appliance or cabinet	☐	☐	☐
SECTION G — BATHROOMS (7 ITEMS)				
43	Mirrors clean and undamaged	☐	☐	☐
44	Tubs and showers clean, caulked, and chip-free	☐	☐	☐
45	Toilets clean, not cracked or scratched, flushing properly	☐	☐	☐
46	Faucets and fixtures clean and operating properly	☐	☐	☐
47	Sinks clean and draining properly	☐	☐	☐
48	No odors — check under sink and around toilet base	☐	☐	☐
49	Bath fans operational	☐	☐	☐
SECTION H — INTERIOR PRESENTATION & LIVING SPACES (8 ITEMS)				
50	Floors clean throughout — no visible damage, debris, or stains	☐	☐	☐
51	Carpets vacuumed; vinyl flooring cleaned	☐	☐	☐
52	Wall panels undamaged — no cuts, blemishes, or visible repairs	☐	☐	☐
53	Ceilings clean throughout — no stains, cracks, or damage	☐	☐	☐
54	All light fixtures and can lights operational	☐	☐	☐
55	Light switches and outlet covers straight and clean	☐	☐	☐
56	Home is clean and neutral — no clutter, personal items, or leftover materials	☐	☐	☐
57	No odors anywhere in home — fresh throughout including closets	☐	☐	☐
SECTION I — CLEANLINESS: TURNOVER & SHOW STANDARD (8 ITEMS)				
58	Cabinet tops and all countertops spotless	☐	☐	☐
59	Cabinets wiped inside and out; shelves dusted	☐	☐	☐
60	Receptacles and light switches wiped down	☐	☐	☐
61	Drawers vacuumed; debris cleared from registers	☐	☐	☐
62	Doors and door knobs wiped down	☐	☐	☐
63	Sinks, bathroom mirrors, tubs, showers, and toilets cleaned	☐	☐	☐
64	All trash removed — inside and outside home	☐	☐	☐
65	Home smells fresh at every point — check closets, bathrooms, under sinks	☐	☐	☐
SECTION J — ESCALATION & FOLLOW-UP (6 ITEMS) — FACILITY MANAGER COMPLETES THIS SECTION				
66	No issues identified — home ready	☐	☐	☐
67	Issues identified — documented in Notes below	☐	☐	☐
68	Issue documented in Rent Manager with photos	☐	☐	☐
69	Regional Manager / Community Manager notified	☐	☐	☐
70	Vendor notified and work order submitted	☐	☐	☐
71	Follow-up date scheduled and confirmed	☐	☐	☐

☐ APPROVED – READY FOR LISTING / SHOWING	☐ NOT READY – ITEMS OUTSTANDING
All items Yes or N/A. Construction sign-off on file.	Do not list or show until all items resolved and sign-offs received.

Sign-off: Facility Manager – Utility & Condition Verification: _____ Date: _____
Community Manager / Sales Representative – Show-Readiness Sign-Off: _____ Date: _____

6.4 Form 4: Listing Form

Completed by: Sales. **QB target table:** Listing Records. **Prerequisite:** Both Construction Inspection and Ops Readiness must be approved. Submission triggers A14 (stage → Listed – Complete).

#	PRE-LISTING VERIFICATION ITEM	YES	NO
SECTION A – RECORD IDENTIFICATION (PRE-POPULATED FROM QB HOME ORDER)			
	Home Order #, Community, Lot #, Listed By, Listing Date – all pre-populated		
SECTION B – PRE-LISTING VERIFICATION (7 ITEMS – ALL MUST BE YES; HARD VALIDATION)			
1	Construction Inspection approved and sign-off on file	☐	☐
2	Ops & Sales Readiness approved and sign-off on file	☐	☐
3	Insurance active in Rent Manager	☐	☐
4	Loan documents uploaded to Rent Manager	☐	☐
5	Serial number confirmed and recorded in Rent Manager	☐	☐
6	Asset status updated in Rent Manager	☐	☐
7	Manufacturer packet confirmed and on file	☐	☐
SECTION C – SUBMISSION			
	Submitted By, Submission Timestamp (auto). **Hard validation:** All 7 items must be Yes. Form cannot be submitted if any item = No.		

7. Integration Architecture

Parakeet Communities operates a three-system stack. **Rent Manager** is the authoritative system of record for all asset identifiers, resident accounts, lease data, and financial ledgers. **Quickbase** is the operational workflow layer – it orchestrates checklist progression, status tracking, and role-based approvals. **FastField** is the mobile field-capture layer for construction and operations inspections. No system replaces another; data flows in one direction per boundary and is never dual-entered.

7.1 Rent Manager → Quickbase (Master Reference Sync)

Rent Manager is not replaced by Quickbase. It remains the canonical source for community names, lot identifiers, unit addresses, and lease records. Quickbase references Rent Manager IDs – it does not replicate financials or lease contracts.

Rent Manager → Quickbase Reference Fields

RM FIELD	QB TABLE	QB FIELD	SYNC DIRECTION	NOTES
Community Name	Communities	Community Name	RM → QB (read-only)	Master reference; never edited in QB
Unit / Lot ID	Lots	Lot ID	RM → QB (read-only)	Primary key linking all QB records
Unit Address	Lots	Street Address	RM → QB (read-only)	Used on FastField form headers
Lease Start Date	Lots	Lease Start	RM → QB (informational)	Displayed; not used in QB gate logic
Resident Name	Lots	Resident Name	RM → QB (informational)	Displayed on Home Ordering record

Sync Method (Open Item O3): The exact sync mechanism — Quickbase Pipeline connector, scheduled export/import CSV, or manual entry at lot setup — is to be confirmed. Until confirmed, community and lot records are created manually in QB at project initiation, with Rent Manager IDs entered as reference fields.

7.2 FastField → Quickbase (Inspection Results Push)

FastField dispatches completed inspection submissions to Quickbase via webhook or REST API call. Each submission maps to a single Quickbase record by Lot ID. The push is one-directional: FastField → QB only. No data flows from QB back into FastField forms after dispatch.

FastField → Quickbase Field Mapping (Key Fields)

FASTFIELD ELEMENT	QB TABLE	QB FIELD	TRANSFORM
Lot ID (header)	Lots	Lot ID	Direct match — links record
Inspector Name	Inspections	Inspector	Direct
Submission Timestamp	Inspections	Completed Date/Time	Auto-populated by FastField
Section pass/fail flags	Inspections	Section Status fields	Yes/No → Passed/Failed
Deficiency photos	Inspections	Photo Attachments	Uploaded as file attachment(s)
Overall Result	Inspections	Inspection Result	Pass / Fail / Conditional Pass
Submission UUID	Inspections	FastField Submission ID	Stored for audit traceability

Hard Validation at Submission: FastField form-level validation fires before the record is transmitted. Any section marked Fail blocks form submission unless the inspector explicitly overrides with a documented reason. Override is logged and visible in QB.

7.3 Quickbase Internal Automation Triggers

Quickbase automations (Pipelines) fire on record events — field changes, new record creation, approval stamps. They are not time-scheduled unless noted. All automation logic relevant to Lot Status progression is specified in Section 5.2 (LS-1 through LS-6). The table below summarises other internal QB triggers relevant to the integration layer.

Quickbase Internal Automation Summary

TRIGGER EVENT	ACTION	DESTINATION
Construction checklist submitted (FastField push received)	Set Lot Status → "Ready for Ops Review"	Lots table
Ops checklist submitted (FastField push received)	Set Lot Status → "Pending Final Approval"	Lots table
Austin stamps Approved on Final Approval record	Set Lot Status → "Ready to Occupy"; notify Melanie	Lots table + email
Any checklist item = Fail on submitted form	Create Deficiency record; assign to responsible role	Deficiencies table
All Deficiency records for a Lot = Resolved	Unlock re-submission flag on checklist	Inspections table
Home Order approved by Austin	Notify John Clark; set Order Status → "In Production"	Home Orders table + email

7.4 Notification Matrix

System Notification Matrix

EVENT	RECIPIENT(S)	CHANNEL	TRIGGERED BY
Construction checklist passed	Justin (Asset Mgmt)	QB email notification	FastField push → QB automation

Ops checklist passed	Austin	QB email notification	FastField push → QB automation
Final approval granted	Melanie (Ops Coord)	QB email notification	Austin approval stamp
Deficiency created	Responsible role (per table assignment)	QB email notification	Auto-created on checklist Fail
Home Order approved	John Clark (Construction)	QB email notification	Austin approval stamp
Lot Status changes	Assigned team member	QB in-app + email	LS automation (LS-1–LS-6)

8. Gate Rules

Gate rules define the precise conditions that must be satisfied before a lot or home order advances to the next workflow stage. Gates are enforced by Quickbase field-level validation and automation logic — no manual override is possible without a documented exception. All gate conditions are AND conditions unless explicitly marked OR.

> **Enforcement Principle:** A gate that can be bypassed is not a gate. Every gate below must be implemented as a hard block in Quickbase — the relevant status field must be locked to the current value until all conditions are satisfied. Soft warnings that allow continuation are not compliant.

8.1 Home Ordering Gates

Home Ordering Gate Conditions

GATE	FROM STAGE	TO STAGE	REQUIRED CONDITIONS (ALL MUST BE TRUE)
HO-G1	Draft	Submitted for Approval	Community selected; Lot ID populated; Home Model selected; Floor Plan selected; Option Package selected; Estimated Delivery Date populated; Submitted By populated
HO-G2	Submitted	Approved / In Production	Austin (Owner) has stamped Approved; Approval Timestamp auto-populated; Order Number assigned
HO-G3	In Production	Delivered to Site	Actual Delivery Date populated; Delivery Confirmation attachment uploaded; Lot ID confirmed match
HO-G4	Delivered	Ready for Construction Inspection	Utility connections confirmed (per checklist Section A); Set-up complete flag = Yes

8.2 Construction Inspection Gates

Construction Inspection Gate Conditions

GATE	FROM STAGE	TO STAGE	REQUIRED CONDITIONS
CI-G1	Ready for Inspection	Inspection In Progress	FastField Construction checklist launched with valid Lot ID; Inspector identity confirmed
CI-G2	Inspection In Progress	Passed (→ Ops Review)	All 89 checklist items = Yes/Pass; No outstanding Fail items; Form submitted via FastField; QB record updated by FastField push
CI-G3	Inspection In Progress	Failed (→ Deficiency Resolution)	One or more checklist items = No/Fail; Deficiency records auto-created; Re-inspection scheduled
CI-G4	Deficiency Resolution	Re-inspection	All Deficiency records for this Lot = Resolved; Resolution notes populated; Resolved By and Resolved Date stamped

8.3 Operations Inspection Gates

Operations Inspection Gate Conditions

GATE	FROM STAGE	TO STAGE	REQUIRED CONDITIONS
OI-G1	Ready for Ops Review	Ops Inspection In Progress	Construction inspection CI-G2 passed; FastField Ops checklist launched with valid Lot ID
OI-G2	Ops Inspection In Progress	Passed (→ Pending Final Approval)	All 71 checklist items = Yes/Pass; Manufacturer packet confirmed on file; Asset status updated in Rent Manager; Form submitted via FastField; QB record updated
OI-G3	Pending Final Approval	Ready to Occupy	Austin approval stamp present; Approval Date/Time auto-populated; Rent Manager unit status updated to Available/Ready

8.4 Lot Status Transition Rules

Lot Status is a single field on the Lots table that summarises the overall readiness state of each lot. It is set exclusively by Quickbase automations (LS-1 through LS-6, defined in Section 5.2) — it is never manually edited. The table below is the authoritative state-machine for Lot Status.

Lot Status State Machine

STATUS VALUE	MEANING	SET BY	NEXT VALID STATUS
Vacant – Available	Lot is empty; no active order	LS-1 / Manual at setup	Home Order Submitted
Home Order Submitted	Austin approval pending	LS-2 on HO record creation	In Production; Vacant – Available (if rejected)
In Production	Home in factory	LS-2 on Austin approval	Delivered to Site
Delivered to Site	Home arrived; construction prep begins	LS-3 on delivery confirmation	Under Construction Inspection
Under Construction Inspection	FastField construction checklist active	LS-3 on checklist launch	Passed Const. Inspection; Failed Const. Inspection
Passed Const. Inspection	Construction checklist passed; awaiting Ops	LS-4 on FastField push (all Pass)	Under Ops Inspection
Failed Const. Inspection	Deficiencies open; re-inspection needed	LS-4 on FastField push (any Fail)	Under Construction Inspection
Under Ops Inspection	FastField ops checklist active	LS-5 on checklist launch	Pending Final Approval; Failed Ops Inspection
Pending Final Approval	Ops passed; awaiting Austin stamp	LS-5 on FastField push (all Pass)	Ready to Occupy
Failed Ops Inspection	Deficiencies open; re-inspection needed	LS-5 on FastField push (any Fail)	Under Ops Inspection
Ready to Occupy	All gates cleared; Rent Manager updated	LS-6 on Austin final approval	Occupied (set in RM); Vacant – Available (if vacated)

9. Build Sequence

The build sequence defines the 16 ordered steps for constructing the Quickbase + FastField system from scratch. Steps are to be executed in order; later steps depend on data structures and configurations created in earlier steps. Estimated effort is provided for planning purposes and assumes one experienced Quickbase builder and one FastField administrator.

> **Prerequisite:** Rent Manager community and lot records must be exported (CSV) before Step 1 begins. Quickbase and FastField accounts must be provisioned with appropriate license tiers for all named users.

Build Sequence — 16 Steps

#	STEP NAME	SYSTEM	DEPENDS ON	DELIVERABLE / DONE CONDITION	EST. EFFORT
1	Create Quickbase Application	QB	—	New QB app "Parakeet Communities" created; admin users provisioned	0.5 hr
2	Build Communities Table	QB	Step 1	Communities table with all fields from Section 3.1; Rent Manager Community IDs imported from CSV	1.0 hr
3	Build Lots Table	QB	Step 2	Lots table with all fields from Section 3.2; relationship to Communities; Rent Manager Lot IDs imported	2.0 hr
4	Build Home Models + Floor Plans + Option Packages Tables	QB	Step 1	Three reference tables from Sections 3.3–3.5 built; relationships linked; seed data entered for all active models/plans/packages	2.0 hr
5	Configure Cascading Dropdowns (Section 3A)	QB	Steps 2, 3, 4	Community → Lot → Model → Floor Plan → Options cascade confirmed; dynamic filter rules operational; Option A/B/C tested per Section 3A.3	3.0 hr
6	Build Home Orders Table + Form	QB	Steps 3, 4, 5	Home Orders table with all fields from Section 3.6; Home Ordering form (Section 4.1) built and tested; cascading dropdowns operational in form context	2.5 hr
7	Build Inspections + Deficiencies Tables	QB	Step 3	Inspections and Deficiencies tables from Sections 3.7–3.8 built; relationships to Lots confirmed	1.5 hr
8	Configure QB Lot Status Automations (LS-1 – LS-6)	QB	Steps 3, 6, 7	All 6 Lot Status automations from Section 5.2 active and tested; state machine verified against Table 8-4	3.0 hr
9	Configure QB Home Order Automations (HO-1 – HO-5)	QB	Steps 6, 8	All Home Order automations from Section 5.1 active; approval routing to Austin confirmed; John Clark notification tested	2.0 hr
10	Configure QB Gate Validations	QB	Steps 6, 7, 8, 9	All gate rules from Section 8 implemented as hard field-level blocks; bypass attempts confirmed blocked in testing	2.0 hr
11	Build QB Role-Based Views and Dashboards	QB	Steps 6, 7, 8	Role dashboards for Austin, John Clark, Justin, and Melanie from Section 4 built; field-level permissions confirmed per Section 2	3.0 hr
12	Build FastField Construction Checklist Form	FastField	Step 3	Construction checklist form (Section 6.1) built with all 89 items across 7 sections; Lot ID header field; hard submission validation	4.0 hr
13	Build FastField Ops Checklist Form	FastField	Step 3	Ops checklist form (Section 6.2) built with all 71 items across 10 sections; Lot ID header field; hard submission validation	3.5 hr
14	Configure FastField → Quickbase Integration	FastField + QB	Steps 7, 12, 13	Webhook or API connection established; field mapping from Table 7-2 confirmed; test submissions received in QB Inspections table	3.0 hr
15	Configure FastField Pre-Populated Launch Links (O11)	FastField + QB	Steps 12, 13, 14	QB report or button generates a FastField launch URL pre-populated with Lot ID and Community; link tested on iOS and Android; confirmed Lot ID passes correctly	2.0 hr
16	End-to-End UAT and Go-Live	All	Steps 1–15	Full workflow tested: Home Order → Approval → Delivery → Construction Inspection → Ops Inspection → Final Approval → Ready to Occupy; all roles sign off; Rent Manager sync verified; go-live approved by Austin	4.0 hr

Total Estimated Build Effort: ~38.0 hours for initial build and UAT. This assumes all Open Items (Section 10) are resolved before Step 5 (cascading dropdowns) and Step 14 (integration) begin. Unresolved Open Items may add scope to Steps 5 and 14.

10. Open Items

Open Items are decisions, confirmations, or clarifications required before the associated build step can be finalised. Each item is assigned an owner and a blocking step. Items marked **Blocking** must be resolved before the referenced build step begins. Items marked **Advisory** can be resolved in parallel without delaying the build.

Open Items Register — v1.2

ID	DESCRIPTION	OWNER	BLOCKS BUILD STEP	PRIORITY	STATUS
O1	Confirm final list of community names and their Rent Manager Community IDs to seed the Communities table	Austin / Justin	Step 2	Blocking	Open
O2	Confirm complete lot roster per community with Rent Manager Lot IDs and current addresses	Austin / Justin	Step 3	Blocking	Open
O3	Confirm Rent Manager → Quickbase sync mechanism: Pipeline connector, scheduled CSV export/import, or manual entry at lot setup	Austin / QB Admin	Step 3	Blocking	Open
O4	Confirm complete Home Model catalogue: all active models, manufacturers, base specs, and whether any models share a floor plan	John Clark	Step 4	Blocking	Open
O5	Confirm all Floor Plan variants per Home Model and which communities each plan is offered in	John Clark	Step 4	Blocking	Open
O6	Confirm the full Option Package catalogue: package names, included options per package, and price deltas (if any) per community	John Clark / Austin	Step 4	Blocking	Open
O7	Confirm the exact cascading filter logic for Option Packages: filtered by community only, or by community + floor plan combination	Austin / John Clark	Step 5	Blocking	Open
O8	Confirm FastField account tier and number of licensed users for Construction and Ops inspection roles	Austin	Steps 12–13	Advisory	Open
O9	Clarify utility alert platform: the Ops checklist (Rehab section, item 14) references an external submission step. Confirm whether this remains a manual out-of-system step, or whether it should be integrated into the QB/FastField workflow. JotForm is not included in this build unless explicitly confirmed.	Melanie / Austin	Step 13	Advisory	Open
O10	Confirm approval chain for edge cases: if Austin is unavailable, who is the designated backup approver for Home Orders and Final Approval?	Austin	Steps 9–10	Advisory	Open
O11	**[NEW v1.2]** Confirm FastField pre-populated launch link mechanism (Step 15): determine whether QB will generate launch URLs via a Pipeline action, a report button, or a custom URL formula field. Test that Lot ID passes correctly into the FastField form header on both iOS and Android devices used in the field.	QB Admin / FastField Admin	Step 15	Advisory	Open
O12	**[NEW v1.2]** Confirm whether "Communities" should be a standalone Quickbase table (as specified in Section 3.1 and Step 2) or managed as a static dropdown list on the Lots table. A standalone table supports future multi-community reporting and scaling; a dropdown is simpler but limits community-level dashboards. Recommendation: standalone table (see Section 3.1 note).	Austin / QB Admin	Step 2	Advisory	Open

Resolution Process: When an Open Item is resolved, update this register with the decision, decision date, and decider. The resolved decision becomes the binding specification for the referenced build step — no further change requests to that step are in scope without a document revision.

10.1 Document Revision History

Document Revision History

VERSION	DATE	AUTHOR	CHANGES
v1.0	Initial	Parakeet AI	Initial build specification for Home Ordering workflow
v1.1	Prior	Parakeet AI	Added Roles section, expanded automations, FastField checklist verbatim items, Open Items O1–O10
v1.2	08/18/26	Parakeet AI	Added Section 3A (Cascading Dropdown Architecture); added Lot Status automations LS-1–LS-6; added Open Items O11–O12; updated Build Sequence to 16 steps; zero MRB references throughout