New Home Delivery

Pre-Delivery Preparation

Before the home arrives:

- **Confirm permits & site readiness**
  - Foundation/pad installed and inspected
  - Utilities (water, sewer/septic, electric) ready for hookup
- **Verify contract details**
  - Make sure specs match what you ordered (model, upgrades, finishes)
- **Schedule delivery date**
  - Coordinate with dealer, transporter, and installer

Initial Inspection

When the home arrives on-site:

- **Be present**
- **Inspect BEFORE signing anything**
  - Exterior: siding, roof, windows, doors, axles/frame
  - Check for transport damage (dents, cracks, loose panels)
- **Take photos/videos of everything**
- **Note issues immediately on delivery paperwork**
  - Do NOT rely on verbal promises

Set & Installation

After delivery, the home is placed and assembled:

- **Placement on foundation**
  - Ensure proper alignment and leveling
- **Marriage line connection** (for multi-section homes)
- **Tie-downs and anchoring**
  - Required for wind/storm safety (especially important in Florida)
- **Utility hookups**
  - Electrical, plumbing, HVAC connections

Installation Inspection

Before final acceptance:

- **Check leveling**
    - Doors/windows should open smoothly
        - Check all windows & doors for operation
    - Floors shouldn't feel uneven

- **Inspect seams & finishes**
    - Walls, ceilings, flooring at connection points
- **Test systems**
    - Lights, outlets, plumbing, HVAC, appliances

Final Walkthrough (Punch List)

This is your most important step:

- Create a **punch list** of defects or incomplete items:
    - Cosmetic (paint, trim, cabinets)
    - Functional (leaks, electrical issues)
- Have the installer/dealer acknowledge the list **in writing**
    - Provide Inspection sheet along with photos of issue to manufacturer for repair
- Set a timeline for repairs from manufacturer

Documentation & Acceptance

Only after satisfied:

- Sign the **completion or acceptance certificate**
- Mail Documents to Parakeet Corporate office:
    - Warranty documents
    - Installation certificates
    - Inspection approvals